BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/20/2017-18 Dated: 23-02-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 8

Name of Work:-Construction of RCC drain & providing covering slab of Jyothinagara in ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Jayanth T	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no142, PWD SR 2016-17)	Cum	206.50	91.05	Rupees Ninety One and Paise Five Only
2	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item	Cum	206.50	103.92	Rupees One Hundred Three and Paise Ninety Two Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Jayanth T	
				Rate	Rate in Words
3	KSRRB M2100 PCC 1 KSRRB M2100 10. Plain cement concrete M10 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications MORTH Specification No. 2100 (P No. 218/27.18)	Cum	39.83	6246.63	Rupees Six Thousand Two Hundred Forty Six and Paise Sixty Three Only
4	Providing laying palin / reinforced cement concrete for Side Drain using M20 normal mix concrete with OPC cement at 300kgs with 20 mm and down size granite metal coarse aggregates @0.69cum and fine aggregates @machine mixed, Well compacted for wall and bottom including centering shuttering Cost of material HOM of machinery curing etc excluding cost of steel as per MORTH Specification No. 1500,1700,2200 walls & bottomof thicknes 15(Page. 265 / Item.No. 37.59.2)	Cum	84.96	7703.61	Rupees Seven Thousand Seven Hundred Three and Paise Sixty One Only
5	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2016-17,p.no17,s.no4.46)	Tonnes	6.63	62958.00	Rupees Sixty Two Thousand Nine Hundred Fifty eight only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Jayanth T	
				Rate	Rate in Words
6	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	265.50	2199.75	Rupees Two Thousand One Hundred Ninety Nine and Paise Seventy Five Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.